BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Providing R O Plant in Jakkur in Ward No.05

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. M C Adarsh	
				In figures	In words
1	41.76	Earth work excavation for foundation of building, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depyh including the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specification No. KBS 2.1 (b)/ 2.3.5 PWD SR 2018-19 It No.2.4 Pg. No.6	Cum	509.12	Rupees Five Hundred Nine And Paise Twelve Only
2	3.36	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2.PWD SR 2018-19 It No.4.2 Pg. No.13	Cum	5889.44	Rupees Five Thousand Eight Hundred Eighty Nine And Paise Forty Four Only
3	4.24	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 PWD SR 2018-19 It No.5.5 Pg. No.25	Cum	5095.71	Rupees Five Thousand Ninety Five And Paise Seventy One Only
4	3.18	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 PWD SR 2018-19 It No.5.6 Pg. No.25	Cum	5211.37	Rupees Five Thousand Two Hundred Eleven And Paise Thirty Seven Only
5	7.06	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, HOM curing complete as per specifications.PWD SR 2018-19, It No.34.12.1	Sqm	159.88	Rupees One Hundred Fifty Nine And Paise Eighty Eight Only
6	8.12	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, ,pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6 PWD SR 2018-19 It No.4.12Pg. No.14	Cum	6854.38	Rupees Six Thousand Eight Hundred Fifty Four And Paise Thirty Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. M C Adarsh	
				In figures	In words
7	0.90	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 500 Specification No.KBS 4.6.3 PWD SR 2018-19 It No.4.46.2Pg. No.18	MT	73033.98	Rupees Seventy Three Thousand Thirty Three And Paise Ninety Eight Only
8	50.81	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 PWD SR 2018-19 It No.4.31Pg. No.16	Sqm	405.93	Rupees Four Hundred Five And Paise Ninety Three Only
9	66.01	Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 PWD SR 2018-19 It No.5.26.1Pg. No.27	Sqm	1034.11	Rupees One Thousand Thirty Four And Paise Eleven Only
10	13.51	Providing 12mm thick cement plaster in single coat with cement mortar 1:4, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.PWD SR 2018-19 It No.15.22Pg. No.116	Sqm	255.13	Rupees Two Hundred Fifty Five And Paise Thirteen Only
11	50.18	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.PWD SR 2018-19 It No.15.9Pg. No.115	Sqm	239.25	Rupees Two Hundred Thirty Nine And Paise Twenty Five Only
12	58.08	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. .PWD SR 2018-19 It No.15.17Pg. No.116	Sqm	277.80	Rupees Two Hundred Seventy Seven And Paise Eighty Only
13	13.51	Providing and fixing Special make glazed Vitrified tiles (Granomite finish) of approved make, quality and colour of size 600x600x10mm thick fixed on existing flooring with a special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete.)PWD SR 2018-19 It No.14.43Pg. No.109	Sqm	1349.33	Rupees One Thousand Three Hundred Forty Nine And Paise Thirty Three Only
14	3.87	Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Specification No.KBS 14.16, 14.17 - Colour glazed tiles 30x60 cms 6mm thick with border of size 30 x 10 cms. PWD SR 2018-19 It No.14.41.2 Pg. No.108	Sqm	1850.51	Rupees One Thousand Eight Hundred Fifty And Paise Fifty One Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. M C Adarsh	
				In figures	In words
15	5.46	Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8 m. Specification No. KBS 7.10 / 7.12. PWD SR 2018-19 It No.7.5 Pg. No.33	Sqm	2956.06	Rupees Two Thousand Nine Hundred Fifty Six And Paise Six Only
16	50.18	Providing and applying two coats with oil bound washable distermper Two Coats of distemper of approved brand and shade on Ceilling & sloped roof including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.PWD SR 2018-19, It No.15.49.1 Pg No.119	Sqm	124.73	Rupees One Hundred Twenty Four And Paise Seventy Three Only
17	58.08	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. PWD SR 2018-19 It No.15.53.1 Pg. No.120	Sqm	100.92	Rupees One Hundred And Paise Ninety Two Only
18	21.00	KSRB 7.9: Providing and fixing M.S Grill work for windows and ventilators using M.S flats or M.S fsquare rods or combination of M.S flat and square rods as per approved deisgn, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materail, fixtures, labour and HOM of machinery complete as per specification. Specification No:KBS 7.12 (P.No:34 Items No:7.9 of PWD SR 2018-19)	Kgs	107.72	Rupees One Hundred Seven And Paise Seventy Two Only
19	36.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 32mm nominal OD pipes PWD SR 2018-19 It No.13.77 Pg. No.96	Mtr	146.27	Rupees One Hundred Forty Six And Paise Twenty Seven Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. M C Adarsh	
				In figures	In words
20	1.00	1.Raw Water pump Qty officer-one number type Mon Block centrifugal operation flow rate -4M3hr operation pressure.4.0kg/cm2 type of drive- phase squirred cage induction motor make-CRI/TEXmo 2.Multigrated sand filter (MSF) Qty offere-one number Type -Top and bottom flow size-15"x65" operation floe rate-4M3/hr Operation pressure-4.0kg/cm2 Type of Modia-Dual-Sand and anthracite Supporting media-Gravels and Silex MOC of shell-FRP Make PARTNER/Aventura 3.Activated Carbon filter (ACF)Qty Offere -one Number Type Top and bottom flow size 16"x65" operation flow rate-4M3/hr operation pressure-3.5kg/cm2 type of Media Activated carbon flakes Type of resin-150kgs MOC of shell-FRP make - PARTNER/Aventura JODINE VALUE-500value 4.Micro Cartridge Filter Nos 5.Antiscalent Dosing UntilQty Offere -one number 6.Multistage Centrifugal pumo high pressure pump Qty Offe-one nos Type-Multistage Centrifugal Operation flow rate-4M3/hr operation pressure-10 to 15kg/cm2 material of construction -SS 316 Make pump-Cri/Kirloskar/unique Type of drive motor-three phase,squired cage indicator KWRPM-2.75/2000(Approx) Make of motor crl/kirloskar 7.R.O Membrane skid consists of (SS 304) a.R.O	Each	1102395.00	Rupees Eleven Lakh(s) Two Thousand Three Hundred Ninety Five Only
21	28.00	supplying heavy gauge pvc conduit pipe... dia confirming to IS 2509 with suitable size benda. Junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall stone structure or rawl plugs in case of brick walls and cement plastering dameged portion using havey gauge saddles at an intereval of 70mm using NF screws (ELE SR 2019-20 Page-2, Item-1.1.2)	mtr	68.24	Rupees Sixty Eight And Paise Twenty Four Only
22	28.00	Suppling... mm dia 2mm/2.5mm thick heavy gauge PVC conduit pipe with suitable size bends, metal/PVC junction boxes adhesive paste etc..., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.(ELE SR 2019-20 Page-2, Item-1.2.2)	mtr	55.64	Rupees Fifty Five And Paise Sixty Four Only
23	23.00	Groove cutting in the wall suppling.. Dia 2mm/2.5mm thick heavy gauge PVC Conduit pipe with bends, metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out conduit wherever necessary.(ELE SR 2019-20 Page-2, Item-1.3.2)	mtr	56.69	Rupees Fifty Six And Paise Sixty Nine Only
24	3.00	Supplying and fixing sheet metal box made out of 18 SWG sheet metal with necessary holes for cable/conduit entry as required with one coat of approved make etc.,.(ELE SR 2019-20 Page-2, Item-1.4.5)	Each	116.54	Rupees One Hundred Sixteen And Paise Fifty Four Only
25	1.00	supplying and fixing PVC/ Metal conduit accessories. (3/5) (ELE SR 2019-20 Page-3, Item-1.5.3)	Each	62.99	Rupees Sixty Two And Paise Ninety Nine Only
26	10.00	Suppling and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work complet. (ELE SR 2019-20 Page-3, Item-1.6.1)	mtr	107.09	Rupees One Hundred Seven And Paise Nine Only
27	12.00	Suppling and wiring adopting loop system in existing PVC Conduit/ casting capping using copper PVC insulated multi strand 2x1.5sqmm copper wire with a 6 Amps flush type SP control switch shall be fixed on the existing plastic sheet / gang box. The outher end of the wires shall be terminated with sufficient loose lenght in a wood / PVC round block. compelete for each outlet. (ELE SR 2019-20 Page-5, Item-2.1.2)	Each	288.72	Rupees Two Hundred Eighty Eight And Paise Seventy Two Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. M C Adarsh	
				In figures	In words
28	.00	Suppling and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos, of machines screws, bolts nuts etc., complete on the existing metal/PVC box,ELE SR 2019-20 Page-9, Item-3.5.3)	No	183.73	Rupees One Hundred Eighty Three And Paise Seventy Three Only
29	2.00	Supplying and fixing of 32 Amps security and energy saving DP switch with key tag suitable to operate on 230 volts, 50Hz AC supply and completely wired on existing box. ELE SR 2019-20 Page-10, Item-3.7)	Each	713.93	Rupees Seven Hundred Thirteen And Paise Ninety Three Only
30	258.00	Wiring for lighting/power circuit using one of pvc insulated 1100v grade, multistrand copper conductor singal core cable in open or concealed system of wiring.ELE SR 2019-20 Page-5, Item-2.3.2) a)1.5sqmm	mtr	21.52	Rupees Twenty One And Paise Fifty Two Only
31	15.00	Supplying and fixing of PVC casing and capping on the wall or ceilng using necessary materials like bends, screws at an interval of 300mm... Etc as required. ELE SR 2019-20 Page-3, Item-1.8.1)	Each	23.10	Rupees Twenty Three And Paise Ten Only
32	16.00	Supplying PVC/GI Flexible conduit pipe.. Mm dia fixing on surface over inverted wooden pugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and either end of the pie terminated completely. ELE SR 2019-20 Page-3, Item-1.9.1)	Each	23.10	Rupees Twenty Three And Paise Ten Only
33	16.00	Extra for supplying 4mm thick white plastic plate and covering for junction boxes of size 110mm conduit using necessary machine screws.. ELE SR 2019-20 Page-10, Item-3.10.2)	Each	11.55	Rupees Eleven And Paise Fifty Five Only
34	25.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 20mm nominal OD pipes. (P.No.99, I.No. 13.86.2 of PWD SR 2018-19)	Rmt	266.46	Rupees Two Hundred Sixty Six And Paise Forty Six Only
35		GST @ 12% (For SR 2018-19 Items Only)			

Contractor

Executive Engineer
Project Division
Yelahanka Zone